PORTFOLIO SAMPLE · TENDER QUALITY RESPONSE

Accessibility Ramps Tender for a UK Train Operator

MARKET	UK
SECTOR	Rail / accessibility equipment
DOCUMENT	Quality response: Service Performance (excerpt)
MY ROLE	Wrote the full submission for a UK manufacturer: selection questionnaire, case studies, quality answers on expertise, service performance, warranty and social value, and the compliance pack.

Wasiu S. · Grant & Bid Writer · UK, US & Australia

Client names, people, locations, reference numbers and pricing have been removed or replaced to protect client confidentiality. Content is otherwise as written for the client.

Question 2: Service Performance

We will keep every ramp on the network safe and in service through planned inspections every six months, one logged route for every fault, and a response model built around the contract Service Levels. Because we designed and built every ramp, the engineer who attends holds the drawings, spare parts and serial history for that ramp, so a Critical Safety Fault can usually be made safe, repaired or replaced on the first visit.

1. BIANNUAL INSPECTION PROCESS

Step	What we do
Plan	Annual schedule issued to the Client, grouped by station cluster. Station managers are notified at least five Business Days before each visit.
Inspect	Each ramp is checked against a standard checklist: deck wear, weld and structural integrity, hinges, latches, grips, wheels, docking station, fixings, locks, labels and coating. Deployment is tested on site.
Fix on the day	Minor defects are fixed during the visit from van stock. Larger defects are logged as faults and prioritised.
Report	Written report within five Business Days. Any safety-critical finding is reported immediately, and always within four hours.
Record	Asset register updated with result and next due date, so no ramp falls out of certification.

2. FAULT PRIORITIES AND RESPONSE

Priority	Example	Acknowledge	Attend	Rectify
Critical Safety Fault	Cracked deck or weld, failed hinge	4 hours	24 hours	2 days
High Priority	Latch or wheel failure, seized lock	1 day	48 hours	5 days
Routine	Worn grip, coating damage, missing label	2 days	5 days	10 days

Every fault is tracked from report to closure with a full audit trail, and escalates from the Service Coordinator to the Service Supervisor and then to the Contract Manager and Managing Director when a Service Level is at risk. Any Critical Safety Fault or repeat fault triggers root cause analysis through our ISO 9001 system, with design changes applied across every affected ramp.

3. MEETING THE SERVICE LEVELS

- Spare ramps held at our facility, with a temporary replacement supplied at no extra charge where a ramp cannot be repaired in place.
- Multiple engineers on call, including evenings, weekends and bank holidays.
- Like-for-like replacements manufactured in-house from drawings held against each serial number.
- Monthly performance report covering KPIs, open faults, Service Credits and improvement actions.